



4'x8'x $\frac{3}{4}$ " fire rated backer board – By Electrician/GC/FC? (typically painted – *this AHJ did not want it painted*)

BDA – by TELECO

2 hr rated room, 90 min door – Structural/GC

5 Dry Contact alarm modules back to the FACP – by Fire Alarm Contractor

Document Box - by Teleco (can be placed next to BDA)

110VAC House power duplex outlet – by electrician

20amp 110V dedicated L5-20 twist-lock receptacle – by electrician

Battery Back Up – by Teleco

$\frac{1}{4}$ "x2"x6" ground bus bar – by electrician